

## **Robertson Restoration**

### **Quotation For:**

Masonry restoration of fieldstone monument and gate wing walls at Aldborough Pioneers' and Soldiers' Memorial Park.

Please accept this quote for your review.

- 100% of mortar joints to be chipped out to a depth of approximately 1 1/2"
- Reset any loose stone units
- Reset stone units that have previously fallen out and are currently stored off site
- 100% repointing of all mortar joints
- Form and pour new 3 1/2" thick reinforced concrete ledge at base of monument, ensuring positive slope for water run-off and 2" overhang with drip cut on the underside (1/2" set back from edge)
- Replace missing stones in gate wing walls where necessary
- Provide and apply penetrating sealer to all masonry surfaces of monument and gate wing walls
- Install hinge anchors into stone columns to accommodate new gate

Allow approximately 30 days to complete work.

Municipality to provide water and hydro.

Labour and materials for the above work provided at a cost of \$18700.00, GST extra.

Thank you for your consideration.

Gino Maniaco  
519-808-1119