



PL	ANT MATERIAL				
KEY	COMMON NAME	BOTANICAL NAME	QTY	SIZE	COND
Δf	CELEBRATION MAPLE	Acer x freemani 'Celzam'	9	60mmcal	WB
Αm	MULTI-STEM SERVICEBERRY	Amelanchier canadensis multi-stem	2	150cm	POT
Ar	RED MAPLE	Acer rubrum 'Sunset'	3	60mmcal	WB
Ca	FLOWERING DOGWOOD	Cornus alba 'Bailho'	3	5gal	POT
DI	PARDON ME DAYLILY	Hemerocallis 'Pardon Me'	60	2yrlgal	POT
Es	SARCOXIE EUONYMUS	Euonymus fortunei 'Sarcoxie'	8	60cm	POT
Gt	SHADEMASTER LOCUST	Gleditsia triacanthos 'Shademaster'	6	60mmcal	WB
Ha	ANNABELLE HYDRANGEA	Hydrangea arborescens 'Annabelle'	13	2yr5gal	POT
Jh	PRINCE OF WALES JUNIPER	Juniperus horizontalis 'Prince of Wales'	П	60cm	POT
K f	KARL FOERSTER REED GRASS	Calamagrostis acutifolia 'Karl Foerster'	8	2yrlgal	POT
Pe	HAMELN FOUNTAIN GRASS	Pennisetum alopecuroides 'Hameln'	10	2yrlgal	POT
Rr	FLOWER CARPET GROUND COVER ROSE	Rosa 'Flower Carpet'	58	60cm	POT
Se	AUTUMN JOY SEDUM	Sedum spectabile 'Autumn Joy'	3Ø	2yrlgal	POT
Th	HICK'S YEW	Taxus x media 'Hicksii'	ΓI	60cm	POT

CONSTRUCTION IMPACT MITIGATION RECOMMENDATIONS FOR TREES

PRE-CONSTRUCTION RECOMMENDATIONS

a) PRIOR TO ANY CONSTRUCTION ACTIVITY, TREE PRESERVATION FENCING IS TO BE INSTALLED AS PER THE TREE PRESERVATION DRAWINGS AND DETAIL.

b) TREES APPROVED FOR REMOVAL ARE TO BE CLEARLY INDICATED IN THE FIELD (MARKED WITH SPRAY PAINT OR OTHER AGREED UPON METHOD) BY THE PROJECT ARBORIST OR LANDSCAPE ARCHITECT PRIOR TO ANY TREE REMOVAL OPERATIONS. ALL REMOVALS TO BE UNDERTAKEN BY AN ISA CERTIFIED ARBORIST.

c) IN ACCORDANCE WITH THE MIGRATORY BIRDS CONVENTION ACT, 1994, ALL REMOVALS MUST TAKE PLACE BETWEEN SEPTEMBER IST AND MARCH 31ST TO AVOID DISTURBING NESTING MIGRATORY BIRDS. IF TREE REMOVAL OCCURS BETWEEN APRIL 1ST AND AUGUST 31ST, A BIOLOGIST IS REQUIRED TO COMPLETE A SEARCH FOR NESTS. ONCE CLEARED, THE CONTRACTOR HAS 48 HOURS TO REMOVE. IF REMOVAL DOES NOT OCCUR WITHIN 48 HOURS, ANOTHER SEARCH WILL BE REQUIRED.

d)CARE SHOULD BE TAKEN DURING THE FELLING OPERATION TO AVOID DAMAGING THE BRANCHES, STEMS, TRUNKS, AND ROOTS OF NEARBY TREES TO BE PRESERVED.

WHERE POSSIBLE, ALL TREES ARE TO BE FELLED TOWARDS THE CONSTRUCTION ZONE TO MINIMIZE IMPACTS ON ADJACENT VEGETATION. ALL REMOVALS TO BE UNDERTAKEN BY AN ISA CERTIFIED ARBORIST.

e) THE EXISTING GROUND-LAYER VEGETATION AT THE BASE OF TREES TO BE PRESERVED IS TO REMAIN INTACT WITHIN THE CRITICAL ROOT ZONE SO AS NOT TO DISTURB

THE SOIL AROUND THE BASE OF THE EXISTING TREES.

f) FINAL SITE GRADING PLANS SHOULD ENSURE THAT THE EXISTING SOIL MOISTURE CONDITIONS ARE MAINTAINED.

RECOMMENDATIONS RELATED TO THE CONSTRUCTION PROCESS

a) TREE PRESERVATION FENCING. IS TO BE MAINTAINED IN GOOD CONDITION AND EFFECTIVE FOR THE DURATION OF CONSTRUCTION UNTIL ALL CONSTRUCTION ACTIVITY IS COMPLETE OR AS PER THE LANDSCAPE ARCHITECT.

b) TREE PRESERVATION FENCING IS TO REMAIN INTACT AS PER THE TREE PRESERVATION DRAWINGS, AND CAN ONLY BE TEMPORARILY REMOVED WITH THE EXPRESS WRITTEN CONSENT FROM THE LANDSCAPE ARCHITECT. SHOULD TREE PRESERVATION FENCING BE TEMPORARILY RELOCATED OR MOVED, IT IS TO BE REINSTATED AS PER THE TREE PRESERVATION PLANS AS SOON AS POSSIBLE.

c) NO CONSTRUCTION, EXCAVATION, ADDING OF FILL, STOCKPILING OF CONSTRUCTION MATERIAL, OR HEAVY EQUIPMENT IS PERMITTED WITHIN THE CRITICAL ROOT ZONE/WITHIN THE TREE PRESERVATION FENCING.

d) WHEN EXCAVATION NEAR A TREE IS REQUIRED, AND IT IS ANTICIPATED THAT ROOTS WILL BE SEVERED AND EXPOSED, DURATION OF EXPOSURE IS TO BE MINIMIZED TO PREVENT ROOT DESICCATION.

e) ROOTS OF TREES TO BE PRESERVED THAT ARE ADJACENT TO SITE EXCAVATION MUST BE CLEANLY CUT, NOT TORN OR ROUGHLY CUT.

f) DURING THE EXCAVATION PROCESS, ROOTS 25MM OR LARGER THAT ARE SEVERED AND EXPOSED SHOULD BE HAND PRUNED TO LEAVE A CLEAN-CUT SURFACE. TO BE UNDERTAKEN BY AN ISA CERTIFIED ARBORIST. EXPOSED SEVERED ROOTS THAT CANNOT BE COVERED IN SOIL ON THE SAME DAY AS THE CUTS ARE MADE ARE TO BE KEPT MOIST. EXPOSED ROOTS ARE TO BE KEPT MOIST BY COVERING THEM WITH WATER SOAKED BURLAP OR ANY OTHER MEANS AVAILABLE TO PREVENT THEM FROM DRYING OUT.

g) AVOID IDLING HEAVY EQUIPMENT UNDER OR WITHIN CLOSE PROXIMITY TO TREES TO BE PRESERVED TO PREVENT CANOPY DAMAGE FROM EXPOSURE TO THE HEAT OF THE EXHAUST.

POST-CONSTRUCTION RECOMMENDATIONS

a) AVOID DISCHARGING RAIN WATER LEADERS ADJACENT TO RETAINED TREES, AS THIS MAY RESULT IN AN OVERLY MOIST ENVIRONMENT WHICH CAN CAUSE ROOT ROT.

b) AFTER ALL WORK IS COMPLETED, TREE PRESERVATION FENCES AND ANY OTHER IMPACT MITIGATION PARAPHERNALIA MUST BE REMOVED.

c) A FINAL REVIEW MUST BE UNDERTAKEN BY THE LANDSCAPE ARCHITECT TO ENSURE THAT ALL MITIGATION MEASURES AS DESCRIBED ABOVE HAVE BEEN MET.






ALL DRAWINGS REMAIN THE PROPERTY OF THE LANDSCAPE ARCHITECT AND SHALL NOT BE REPRODUCED OR REUSED WITHOUT THE LANDSCAPE ARCHITECTS WRITTEN PERMISSION.


THIS DRAWING SHALL NOT BE USED FOR CONSTRUCTION OR TENDER PURPOSES UNLESS SIGNED AND DATED BY RONALD H. KOUDYS, OALA, CSLA, LANDSCAPE ARCHITECT, LONDON, ONTARIO (519) 667-3322.

PLOTTING INFORMATION:

PLOTTED DATE = JAN.17.2022

PLOTTED SCALE = 1:1





PROJECT TITLE:


'THE 525'
APARTMENT DEVELOPMENT
177 VICTORIA STREET


RODNEY, ONTARIO

DRAWING TITLE:

LANDSCAPE PLAN

DATE:	SCALE:	DRAWING No.
JANUARY 2022	AS NOTED	
DRAUN: RKLA Inc.	CHECKED BY:	
PROJECT No.		
22-		






ALL PERENNIALS TO BE PLANTED A MINIMUM OF 12m ON CENTER AWAY FROM ALL BUILDING

PERENNIAL PLANTING DETAIL - N.T.S.

ALL DIMENSIONS SHOWN IN MILLIMETERS.

. INSTALL 15MM OF APPROVED MULCH.


EDGES UNLESS OTHERWISE NOTED




- EXISTING TREES ARE TO BE PROTECTED FROM CONSTRUCTION WITH THE INSTALLATION OF A 1200MM (4'-0") HIGH SNOW FENCE, HELD IN PLACE WITH 1800MM (6'-0") 'T-BAR'.
 THE BARRIER IS TO BE INSTALLED PRIOR TO ANY CONSTRUCTION AND MUST REMAIN IN PLACE UNTIL ALL CONSTRUCTION IS COMPLETED. ALL SUPPORTS AND BRACING SHOULD BE INSIDE THE TREE PROTECTION ZONE. ALL SUCH SUPPORTS SHOULD MINIMIZE DAMAGING ROOTS IN THE TREE PROTECTION ZONE. NO CONSTRUCTION ACTIVITY, GRADE CHANGES, SURFACE TREATMENT, OR EXCAVATION OF AN
- KIND IS PERMITTED WITHIN THE TREE PROTECTION ZONE. NO MOVEMENT OF EQUIPMENT, STORAGE OF BUILDING SUPPLIES, CLEANING OR EQUIPMENT, R DUMPING OF SOLVENTS, GASOLINE, ETC., MAY OCCUR WITHIN THIS FENCE LINE. WHERE HIGH QUALITY SPECIMENS OCCUR ADJACENT TO AREAS SUBJECTED TO INTENSIVE CONSTRUCTION ACTIVITY, WOODEN CRIBBING SHOULD BE INSTALLED TO PROTECT TRUNKS ROM DAMAGE IN THE EVENT THAT HEAVY EQUIPMENT BREAKS DOWN THE SNOW FENCING. FENCE TO BE INSPECTED BY ENVIRONMENTAL CONSULTANT ON A REGULAR BASIS AND BE

TEMP. TREE PROTECTION BARRIER - N.T.S.

MAINTAINED BY THE SUBDIVIDER / BUILDER.



LIMESTONE PATH DETAIL - N.T.S.




- SEE NOTE #11


- SEE NOTE #12


PLAN VIEW (NEXT TO BUILDING)


DEPTH OF 150mm

OTHERWISE









GENERAL PLANTING SPECIFICATIONS:

- BASE INFORMATION SUPPLIED BY Y.C. LIU ENGINEERING.
- ENGINEERING INFORMATION SUPPLIED BY Y.C. LIU ENGINEERING. CONTRACTOR TO MAKE THEMSELVES FAMILIAR WITH ALL RELATED SPECIFICATIONS.
- CONTRACTORS ARE RESPONSIBLE FOR REVIEW OF ALL SPECIFICATIONS AND RELATED DRAWINGS WITH SELECTED SUB-CONTRACTORS AS THEY PERTAIN TO WORK AS OUTLINED ON LANDSCAPE ARCHITECTURAL WORKING DRAWINGS AND SPECIFICATIONS.
- REPORT ALL DISCREPANCIES TO THE LANDSCAPE ARCHITECT DURING TENDERING PROCESS, ERRORS AND/OR OMISSIONS WILL BE THE
- CONTRACTOR SHALL MAINTAIN ALL LANDSCAPED AREAS UNTIL OWNER ACCEPTANCE OF PROJECT. CONTRACTOR TO NOTIFY LANDSCAPE ARCHITECT IN WRITING ON COMPLETION OF PROJECT FOR A SITE WORK COMPLETION CERTIFICATE AS WELL AS THE COMMENCEMENT OF THE ACCEPTANCE OF PROJECT.
- ALL WORKMANSHIP TO BE WARRANTIED FOR ONE YEAR UNLESS OTHERWISE STATED. WARRANTY PERIOD WILL BEGIN ON FINAL
- ACCEPTANCE OF PROJECT. ALL WORKMANSHIP TO COMPLY WITH THE CANADIAN LANDSCAPE STANDARDS.
- ALL NURSERY STOCK TO BE #1 NURSERY GROWN AND MUST COMPLY WITH THE CANADIAN NURSERY LANDSCAPE ASSOCIATION'S "CANADIAN NURSERY STOCK STANDARD", LATEST EDITION. 10. ALL LANDSCAPING IS TO BE INSTALLED PRIOR TO THE END OF THE FIRST GROWING SEASON FOLLOWING THE OCCUPANCY OF THE SITE
- DEVELOPMENT UNLESS OTHERWISE STATED. CONTRACTOR IS RESPONSIBLE FOR ALL UNDERGROUND UTILITIES AND MUST SUPPLY THE LANDSCAPE ARCHITECT WITH COPIES OF LOCATE

GRADING I. CONTRACTOR TO ENSURE POSITIVE DRAINAGE IN ALL AREAS.

CERTIFICATES PRIOR TO COMMENCEMENT OF WORK.

- ALL GRADING TO BE IN ACCORDANCE WITH SITE ENGINEERS DRAWINGS.
- SOIL SHALL BE SCARIFIED FREE OF ALL STONES, ROOTS, BRANCHES LARGER THAN I" (25MM) AND COMPACTED TO 85% S.P.D. ALL SUBSOIL TO BE SCARIFIED TO A DEPTH OF 6" (150 MM) PRIOR TO THE INSTALLATION OF TOPSOIL TO ENSURE NO HARDPAN
- CONTRACTOR TO NOTIFY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION OF TOPSOIL TO APPROVE SUBBASE.
- DIRECT ALL RAINLEADERS AND SUMP LEADERS AWAY FROM PLANTING BEDS AND TO THE DESIGNATED SWALES.

NOTIFY LANDSCAPE ARCHITECT IN WRITING OF ANY SUBSTANTIAL WET CONDITIONS.

AT THE CONTRACTORS EXPENSE A SOIL TEST IS TO BE COMPLETED BY A REPUTABLE LABORATORY. THE SOIL TEST IS TO BE COMPLETED AND IF NECESSARY, RECOMMENDATIONS FROM THE LABORATORY ARE TO BE INCLUDED. THE RESULTS OF SOIL TESTS AND RECOMMENDATIONS ARE TO BE PROVIDED TO THE LANDSCAPE ARCHITECT FOR APPROVAL ONE WEEK PRIOR TO WORK COMMENCING. TOPSOIL FOR PLANTING BEDS IS TO BE A FERTILE, FRIABLE, NATURAL LOAM TO A MINIMUM DEPTH OF 18" (450MM), AND A MINIMUM DEPTH OF 4" (100MM) FOR TURF AREAS - UNLESS OTHERWISE STATED - TOPSOIL SHALL CONTAIN NOT LESS THAN 4% ORGANIC MATTER FOR CLAY LOAMS AND NOT LESS THAN 2% ORGANIC MATTER! FOR SANDY LOAM TO A MAXIMUM OF 15%, AND CAPABLE OF SUSTAINING VIGOROUS

PLANT GROWTH, FREE OF SUBSOIL CONTAMINATION, ROOTS AND STONES OVER 50MM DIAMETER, REASONABLY FREE OF WEEDS, AS DETERMINED BY THE LANDSCAPE ARCHITECT , AND HAVING A pH RANGING FROM 6.0 TO 1.0.

ALL TREEPITS, SHRUB PITS AND PLANTING AREAS ARE TO BE MULCHED UNLESS OTHERWISE NOTED.

CONTRACTOR TO INSTALL 3" (15MM) OF 'GRO-BARK' MEDIUM MULCH IN ALL AREAS. ALTERNATIVES MAY BE ACCEPTED - CONTRACTOR TO PROVIDE 3 SAMPLES FOR WRITTEN APPROVAL TO THE LANDSCAPE ARCHITECT.

CONTRACTOR TO VERIFY ALL PLANT MATERIAL ON DRAWING(S) AND PLANT MATERIAL LIST(S). REPORT ALL DISCREPANCIES AT TENDERING PROCESS. SUBSTITUTIONS WILL NOT BE ACCEPTED WITHOUT WRITTEN CONFIRMATION BY THE LANDSCAPE ARCHITECT.

- PLANTINGS MAY BE ADJUSTED TO SUIT UTILITIES STRUCTURES AND AESTHETIC CONCERNS, ADJUSTMENTS ARE TO BE MADE UNDER THE DIRECTION OF THE LANDSCAPE ARCHITECT. ADJUSTMENTS TO PLANTING WITHOUT CONSENT OF LANDSCAPE ARCHITECT AND OR PROJECT MANAGER MAY NOT MEET INTENT OF DESIGN AND OR MUNICIPAL APPROVALS. PLANT MATERIAL THAT HAS TO BE RELOCATED AS A RESULT WILL BE AT THE COST OF THE CONTRACTOR.
- 4. LANDSCAPE ARCHITECT TO INSPECT ALL PLANT MATERIAL ON SITE OR AT ITS SOURCE PRIOR TO INSTALLATION. CONTRACTOR IS TO GIVE LANDSCAPE ARCHITECT 48 (HRS) NOTICE FOR INSPECTION. CONTRACTOR TO NOTIFY LANDSCAPE ARCHITECT IN WRITING IF ADVERSE WEATHER MAY IMPACT THE HEALTH OF THE PLANT MATERIALS AT
- TIME OF PLANTING. IE. TEMPERATURE, PRECIPITATION. ALL TREE PITS SHALL BE AT LEAST 2 FT. (600MM) WIDER THAN BALL OF THE TREE TO BE PLANTED AND SHALL BE DEEP ENOUGH 50
- HAT THE TOP OF BALL 19 AT THE SAME LEVEL AS SURROUNDING GRADE. A MINIMUM OF 6" (150MM) OF BACKFILL SHALL BE PLACED UNDER BALL. TREE PITS ARE NOT TO BE LEFT OPEN OVER NIGHT
- SHRUB BEDS SHALL BE EXCAVATED TO A DEPTH OF 18" (450MM) AND FILLED WITH APPROVED BACKFILL MATERIAL. SHRUB BEDS ARE NOT TO BE LEFT OPEN OVER NIGHT.
- 8. ALL TREES SHALL HAVE AN EARTH SAUCER AT ITS BASE WITH A DIAMETER AS LARGE AS EXCAVATED AREA AND SHAPED TO RETAIN WATER (SEE DETAIL). EARTH SAUCER TO HAVE APPROVED MULCH INSTALLED TO A MINIMUM DEPTH OR 2.5" (63MM).
- ALL BURLAP SHALL BE CUT AND BURIED BELOW SURFACE DURING PLANTING. . ALL EVERGREENS ARE TO WRAPPED THE FIRST WINTER AT THE EXPENSE OF THE LANDSCAPE CONTRACTOR.
- ALL SHRUBS PLANTED WITHIN IM OF SALTED ROADWAYS, PARKING AND SIDEWALKS TO BE PROTECTED WITH SILT FENCING THROUGHOUT THE FIRST WINTER AFTER INSTALLATION AT THE EXPENSE OF THE LANDSCAPE CONTRACTOR (OPTIONAL)
- DIRECT ALL RAINLEADERS AND SUMP LEADERS AWAY FROM PLANTING BEDS AND TO DESIGNATED DRAINAGE SWALES.
- 13. DO NOT INSTALL PLANT MATERIAL IN DRAINAGE SWALES. 14. CONTRACTOR IS TO REMOVE ALL STAKES AND GUY WIRES AFTER 2 FULL GROWING SEASONS.

- ALL LANDSCAPED AREAS TO BE SODDED TO THE STREET CURB (S) UNLESS OTHERWISE STATED. CONTRACTOR TO ENSURE (WHERE APPLICABLE) ALL PLANTING BEDS ADJACENT TO TRAFFIC ISLANDS, INTERIOR SITE CURBING, AND
- SIDEWALKS HAVE A 3'0"(IOM) SOD MAINTENANCE STRIP INSTALLED. ANY SODDING OR WORKS ON LANDS ABUTTING THE PROPERTY FROM THE LOTLINES TO SIDEWALK AND CURBING, SHALL BE COMPLETED
- OR REPAIRED TO THE SATISFACTION OF THE LANDSCAPE ARCHITECT, CITY, AND OR REGIONAL MUNICIPALITY UNLESS OTHERWISE STATED. SOD SHALL BE CERTIFIED * I CULTIVATED TURF GRASS, GROWN AND SOLD IN ACCORDANCE WITH THE CLASSIFICATIONS OF THE NURSERY SOD GROWERS ASSOCIATION OF ONTARIO. AT TIME OF SALE IT SHALL HAVE A STRONG FIBROUS ROOT SYSTEM AND SHALL BE CUT IN PIECES APPROXIMATELY ONE SQYD (900 M2) IN AREA WITH THE SOIL PORTION BEING 3/4" IN(19MM).
- SOD TO BE FERTILIZED AT THE APPROPRIATE RATES AS INDICATED BY SOIL TESTS COMPLETED BY A REPUTABLE SOILS LABORATORY. 6. UPON INSTALLATION AREAS SHOULD BE WATERED SO AS TO SATURATE SOD AND THE UPPER 4" (100MM) OF BACKFILL TOPSOIL. AFTER
- SOD AND SOIL HAVE DRIED SUFFICIENTLY TO PREVENT DAMAGE, IT SHALL BE ROLLED WITH A ROLLER PROVIDING 1 500 LBS. (681KG)
- 1. CONTRACTOR TO REPAIR ALL DAMAGED AREAS TO THE SATISFACTION OF THE LANDSCAPE ARCHITECT AND OR CLIENT.

I. DURING THE WARRANTY PERIOD, BETWEEN MAY 15 AND SEPTEMBER 15 OF EACH YEAR, WATERING OF ALL PLANTS SHALL BE CARRIED OUT NO LEGS THAN 6 TIMES PER YEAR, IN ACCORDANCE WITH THE WATERING SCHEDULE TO BE DETERMINED BY THE OWNER, UNLEGS OTHERWISE

- STATED ON THE DRAWINGS. CRITICAL WATERING MONTHS ARE JUNE, JULY & AUGUST. 2. IF NO AUTOMATED IRRIGATION SYSTEM HAS BEEN PROVIDED FOR WATERING OPERATIONS, CONTRACTOR TO PROVIDE WATER TO THE SITE IF HOSE BIBS WITHIN THE BUILDING ENVELOPE ARE NOT AVAILABLE.
- 3. MANUAL WATERING SHOULD ENSURE DEEP WATERING OF TREES, SHRUBS, GROUND COVERS AND GRASSED AREAS, WATERING OF GRASSED AREAS TO COMMENCE ON A REGULAR BASIS AND CONTINUE WITH INTENSITY DEPENDING ON AMOUNT OF RAINFALL. NEW SOD THAT HAS BEEN LAID SHOULD BE KEPT MOIST FOR 4 TO 5 WEEKS OR UNTIL IT HAS FIRMLY ROOTED INTO THE EXISTING SOIL. 4. ALL CONIFEROUS TREES SHALL BE WATERED IN LATE FALL, JUST PRIOR TO FREEZE-UP.
- WATER SHALL BE APPLIED SO THAT THE WASHING OF THE SOIL OR DISLODGING OF MULCH OR TREE GUARDS DOES NOT OCCUR. DAMAGE SHALL BE IMMEDIATELY REPAIRED TO THE SATISFACTION OF THE OWNER AT NO ADDITIONAL COST.



KEY MAP 🕀




ALL DRAWINGS REMAIN THE PROPERTY OF THE LANDSCAPE ARCHITECT AND SHALL NOT BE REPRODUCED OR REUSED WITHOUT THE LANDSCAPE ARCHITECTS WRITTEN PERMISSION.

THIS DRAWING SHALL NOT BE USED FOR CONSTRUCTION OR TENDER PURPOSES UNLESS SIGNED AND DATED BY RONALD H. KOUDYS, OALA, CSLA, LANDSCAPE ARCHITECT, LONDON, ONTARIO (519) 667-3322.

Ronald H. Koudys, O.A.L.A. C.S.L.A. DATE ISSUED FOR SPA JAN.17.2022 JAN.10.2022 ISSUED FOR REVIEW DATE DESCRIPTION

PLOTTING INFORMATION: PLOTTED DATE = JAN.IT.2022 PLOTTED SCALE = 1:1



PROJECT TITLE:

'THE 525' APARTMENT DEVELOPMENT 177 VICTORIA STREET RODNEY, ONTARIO

DRAWING TITLE:

LANDSCAPE DETAILS

DATE:	SCALE:	DRAWING No.
JANUARY 2022	AS NOTED	
DRAWN:	CHECKED BY:	
RKLA Inc.	RHK.	
PROJECT No.		
22-		